

# BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineer  
Byatarayanapura Division  
B.B.M.P., Bangalore - 92

## DRAFT TENDER SCHEDULE

Name of work: Estimate for Improvements to Road and Drains at Agrahara Village in ward No 05  
Byatarayanapura Sub Division

| Sl. No. | Quantity. | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Unit | Rates      |                                                                         |
|---------|-----------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|------------|-------------------------------------------------------------------------|
|         |           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |      | In Figures | In Words                                                                |
| 1       | 273.46    | KSRB 2-1.1: Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications, Specification No KBS 2.1(a) / 2.3.1, with all lead and lift etc complete as per                                                                            | cum  | 126.36     | Rupees One Hundred Twenty Six And Paise Thirty Six Only                 |
| 2       | 183.00    | KSRB-4-1.3 : Providing and laying in position <b>plain cement concrete of mix M 7.5</b> with OPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1.4.2, with all lead and lift etc complete as per specifications and directions of engineer in charge of the work.                       | Cum  | 4290.84    | Rupees Four Thousand Two Hundred Ninety And Paise Eighty Four Only      |
| 3       | 48.80     | KSRB 4-6.7 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1 m in depth including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 with all lead and lift etc complete as per specifications and directions of engineer in charge of the work.                                                                                                                                                       | Sqm  | 244.08     | Rupees Two Hundred Forty Four And Paise Eight Only                      |
| 4       | 122.00    | Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC) for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 for raft foundation, column footing, main and secondary beams. with all lead and lift etc complete as per specifications and directions of engineer in charge of the work. | Cum  | 6464.88    | Rupees Six Thousand Four Hundred Sixty Four And Paise Eighty Eight Only |
| 5       | 260.00    | KSRRB M2600-3: (ii) Providing & fixing 20 mm thick compressible fibre board in expansion joint complete as per drawing & technical specification complete as per specifications, MORTH specification No. 2605, with all lead and lift etc complete as per specifications and directions of engineer in charge of the work.                                                                                                                                                                                                                                                                                | M    | 137.16     | Rupees One Hundred Thirty Seven And Paise Sixteen Only                  |
| 6       | 1220.00   | Vaccum De- writing with vaccum pump and suction mat and compaction with skin flater clubbed with floatiing disc including cost of generator, HOM of machinery Sereed Vibratory Power Floaterblade and diisc etc. with all lead and lift with all lead and lift etc complete as per specifications and directions of engineer in charge of the work.                                                                                                                                                                                                                                                       | Sqm  | 91.80      | Rupees Ninety One And Paise Eighty Only                                 |



| Sl. No. | Quantity. | Description                                                                                                                                                                                                                                        | Unit | Rates      |                                        |
|---------|-----------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|------------|----------------------------------------|
|         |           |                                                                                                                                                                                                                                                    |      | In Figures | In Words                               |
| 7       | 273.46    | Lead for Disposal of Debris shall be payable at carage rates by Mechanical means including loading and unloading. From 0.00 to 2.00 Km with all lead and lift etc complete as per specifications and directions of engineer in charge of the work. | Cum  | 62.20      | Rupees Sixty Two And Paise Twenty Only |

Signature of the Contractor

Assistant Executive Engineer  
Byatarayanapura Sub-division  
KRIDL BBMP, Bangalore

ಶರಣಿ ಕೆಲಸದ ಮೊತ್ತವನ್ನು  
ಅಧಿಕಾರಿಗಳ ಸಂಖ್ಯೆ.....  
ಅಧಿಕಾರಿಗಳ ಸಂಖ್ಯೆ/ಇಲ್ಲದ  
ಅಧಿಕಾರಿಗಳ ಸಂಖ್ಯೆ  
Superintending Engineer  
Yelahanka Zone  
BBMP, Bangalore

Executive Engineer  
Byatarayanapura Division  
BBMP, Bangalore - 92